

Grace Towers - Heat Recovery with Flow Adjustment

Measured total heat recovery is approximately 8.1% higher than expected at Grace Towers. The combined rating for two Yanmar units is 404 MBtu/h, while measured total heat recovery is upwards of 439.6 MBtu/h. To correct both useful and rejected system heat recovery, the flow was reduced by 8.1%, which was calculated by dividing the rated by the measured total heat recovery.

